REVIEW OPTIONS FOR SCREEN FENCE

TW 128.00

sloped walk

TW 123.00

120.78

TW 123.00

TW 126.00

TW 128.00

sloped walk

TW 121.00

TW 124.00

TW 124.00

4%

LAWN

120

119.90±

ENTRY WALKWAYS: CITY HALL BRICK PAVERS TYP.

PARKING LOT

sloped walk

2%

LAWN

21 abv

6 APW

TW 119.50

119.50±

10 IC

1 IBP

RAMP

CRUSHED STONE MULCH AROUND BASE OF EXISTING TREE

4%

119

ENTRY WALKWAYS: CITY HALL BRICK PAVERS TYP.

120.00±

STONE LANDING

WALKWAY

118.50±

9 BGM

hkr

1 IBP

LAWN

PORCH

1 FG

5 VC

4 RBK

STEPS: STONE RISERS W/ 2" BLUESTONE TREADS; BLUESTONE LANDING

1 AS

4 BGM

120.00±

+119.78

6 an

LAWN

ex.wall to remain

116.25±

EXISTING TERRACE STEPS AND WALL TO REMAIN

LAWN

RE-BUILD LOW FIELDSTONE RETAINING WALL: MATCH EXISTING WALL CHARACTER

4" CLAY

MH RIM=109.5 INV IN=108.0 INV OUT=107.4±

0 08 16

LANDSCAPE MATERIALS

BRICK WALKWAYS AND TERRACE PAVING TYP.
BLEND OF NEW AND SALVAGED CLAY BRICK PAVER; CITY HALL PAVERS TYP.
HAND TIGHT JOINTS TO BE SWEPT W/ POLYMERIC SAND

SETTING BED - COMPACTED SUB-GRADE, MIN. 6" OF COMPACTED AGGREGATE / GRAVEL BASE OVER GEO-TEXTILE FILTER FABRIC WITH 1" COURSE SAND SETTING BED; 3/8" JOINTS SWEPT WITH GRAY POLYMERIC STONE DUST TYP.;

Landscape Plan
Old Derby Academy
34 Main St., Hingham, MA

SEAN PAPICH
landscape architecture

222 north street hingham,ma 02043
T781.741.5455 www.seanpapich.com

DATE: December 02, 2014
February 08, 2016, rev.
February 24, 2016, rev.
June 03, 2016; rev.
August 09, 2016; rev.

SCALE: 1/8" = 1'-0"